International Construction Equipment
301 Warehouse Drive
Matthews, NC 28104
Phone: 704 821-8200
Email info@iceusa.com

ICE® Pile Driving Leads

Durable • Versatile

Engineered and fabricated to provide maximum strength-to-weight ratio for superior pile rig performance.

- High-strength structural tube front guide-rails for abrasion resistance and long life.
- Braced rear tubes are structurally matched with front rails to provide equal moment capacity for both fore and aft batter conditions.
- Rigid-bolted connections provide maximum stability and quick set-up.
- Available in various sections for maximum flexibility and ease of transport.
- All sections precision-fabricated in production jigs to maintain strict dimensional tolerances that ensure accurate connection and alignment on-site.
- Each section fitted with full-length ladder for easy equipment access.
- Swinging, fixed or sliding configurations available to meet any job requirement.

Accessories include (left) universal 2-axis boom point connector, (middle) 3-axis rooster sheave assembly, (right) head-block with optional auger bracket.

International Construction Equipment, Inc.
301 Warehouse Drive
Matthews, NC 28104
888 ICE-USA1 | www.iceusa.com

ICE® Pile Driving Leads - Specifications



	20 in. leads	26 in. leads	32 in. leads	42 in. leads
A	39.5	45.5	52.5	68.5
B	35.5	41.5	48.5	64.5
C	28.5	34.5	40.5	54.5
D	20.5	26.5	32.5	42.5
E	18.8	20.8	31	35
F	8	8	8	8
G	34.1	36.1	48.6	53.8

	36 in. leads
B	50.5
C	43
D	26
E	21
F	6
G	62

Description & Weight by Size	20 in. leads	26 in. leads	32 in. leads	36 in. leads	42 in. leads
16' Top Section with lifting bail assembly	1,170	1,495	2,288	-	-
32' Top Section with lifting bail assembly	-	2,990	4,685	-	-
40' Top Section with lifting bail assembly	-	-	-	7,055	-
4' Intermediate section	-	570	-	-	-
8' Intermediate section	662	947	1,427	-	-
16' Intermediate section	1,250	1,660	2,648	3,272	-
40' Intermediate section	-	-	-	7,094	-
4' Stab point bottom section	-	-	-	-	-
20' Stab point bottom section	1,406	1,930	3,000	-	-
40' Stab point bottom section	-	-	1,427	-	-
2' Fixed boom-point section	-	670	-	-	-
3' Fixed boom-point section	-	-	1,400	-	-
Universal 2-axis boom-point connector	-	1,150	1,150	-	-
Rooster sheave (3 lines x 8" diameter	-	150	150	-	-
Headblock (4 sheaves for 2 lines)	-	1,200	1,400	-	-
Headblock (6 sheaves for 3 lines)	-	1,330	1,530	-	-
Headblock with auger bracket (2 lines plus auger line)	-	1,750	2,000	-	-
16' long sliding box track with clamp-plates, bolts, nuts	-	1,075	1,423	-	-
Sliding boom point box	-	897	1,115	-	-
Lifting box with 3 sheaves	-	448	616	-	-
Spotter sliding box	-	361	438	-	-
Lead side auger guides	-	33 lbs/ft	33 lbs/ft	-	-
Lifting angles (pair, bolt on)	-	-	-	-	300
36" pipe pile guide (bolt on)	-	-	-	-	1,550

International Construction Equipment, Inc.
301 Warehouse Drive
Matthews, NC 28104
888 ICE-USA1 | www.iceusa.com

"Due to improvements to ICE manufactured products and the EPA mandated Tier III emission regulations, unit specifications are subject to change without notice. Please contact ICE engineering department to confirm possible changes."